ADDENDUM NUMBER 01

Owner: Sabine River Authority

Project: Iron Bridge Dam Rock Riprap Repair Phase 2 RFB #25-0301

Project No.: SRA22667

Addendum No. 01

Addendum Date: August 5, 2024

The following additions, deletions, modifications, or clarifications shall be made to the appropriate portions of the Contract Documents. Offerors must acknowledge receipt of this Addendum in the space provided on the Bid Form, Article 5.03.



ARTICLE 1 – ADDENDUM

1.01 Amend the Contract Documents

A. Make the additions, modifications, or deletions to the Contract Documents described in this Addendum.

1.02 Acknowledge Addenda

A. Acknowledge receipt of this Addendum in the Bid Form submitted for this Project. Failure to acknowledge receipt of this addendum in the Bid Form may render the Bid as non-responsive and serve as the basis for rejecting the Bid.

ARTICLE 2 – SPECIFICATIONS

2.01 Section C-410 Bid Form for Construction Contract

A. Article 3 Basis of Bid – Lump Sum and Unit Prices

Clarification for Bid Item 3:

The 1,800 tons of rock riprap listed is the estimated amount of rock that will be required in this area. The 1,800 tons is included in the 22,500 tons of total rock to be placed.

2.02 Section C-520 Agreement between Owner and Contractor for Construction Contract

Article 4 Contract Times Paragraph 4.03 A.

A. Modify the paragraph to read as follows:

"The Work will be substantially complete within **300** consecutive calendar days after the date when the Contract Times commence to run as provided in Paragraph 4.01 of the General Conditions, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions within **330** consecutive calendar days after the date when the Contract Times commence to run for the bid."

ARTICLE 3 – DRAWINGS

3.01 Sheet No. G-2 Sequence 3 of 6 – General Notes

A. Add the following general notes:

"24. THE ROCK RIPRAP STOCKPILE LOCATED ON THE NORTH SIDE OF THE RAMP ROAD HAS SOME SOIL MIXED IN WITH THE ROCK. CONTRACTOR SHALL MAKE AN EFFORT TO SEPARATE THE SOIL FROM THE ROCK PRIOR TO LOADING IT FOR PLACEMENT."

3.02 Sheet No. C-1 Sequence 4 of 6 – Site Plan

A. Add the following note to Note 8:

"TEMPORARY RAMP, IF UTILIZED, MAY NOT BE EXCAVATED INTO THE EMBANKMENT. RAMP MAY BE CONSTRUCTED BY ADDING FILL TO THE EMBANKMENT TO PROVIDE ACCESS TO THE 1,000-FOOT SECTION TO BE REPAIRED. CONTRACTOR SHALL SUBMIT PLANS FOR THE RAMP TO ENGINEER FOR APPROVAL PRIOR TO BEGINNING CONSTRUCTION. THE RAMP SHALL BE REMOVED AT THE COMPLETION OF CONSTRUCTION AND THE AREA GRASSED, UNLESS APPROVED BY THE OWNER TO REMAIN IN PLACE."

B. Add the following notes:

"9. IT IS ANTICIPATED THAT ROCK WILL NEED TO BE HAULED FROM THE STOCKPILE ADJACENT TO THE SPILLWAY TO BE PLACED ON THE OTHER END OF THE DAM.

10. THE CONTRACTOR MAY CONSTRUCT A FLEXBASE TURNAROUND AT THE END OF THE ROCK PLACEMENT AREA (STA 309+00) TURNAROUND SHALL BE REMOVED AT THE COMPLETION OF CONSTRUCTION AND THE AREA GRASSED. TURNAROUND SHALL NOT BE AN ITEM OF DIRECT PAY BUT SHALL BE SUBSIDIARY TO OTHER ITEMS BID."

END OF SECTION