

March 8, 2023

**ADDENDUM NO. 2
SABINE RIVER AUTHORITY OF TEXAS
Lake Fork Fence Improvements RFB# 23-0701**

THIS ADDENDUM IS ISSUED FOR THE PURPOSE OF AMENDING THE CONTRACT DOCUMENTS FOR THE SABINE RIVER AUTHORITY OF TEXAS, AS FOLLOWS:

Notice to Bidders

- The bid date is hereby revised. Replace the first paragraph of the notice with the following:


The Sabine River Authority of Texas (SRA) is seeking bids for labor, materials, and equipment to perform Fence Improvements in the proposed locations on Lake Fork. Sealed bids are to be received in the office of the Division Manager, Sabine River Authority of Texas (SRA) Lake Fork Division Office at 353 Private Road 5183, Quitman, TX 75783 for response to this request for bid, until **10:00 a.m. THURSDAY, March 16, 2023.** Bids will, immediately thereafter, be publicly opened and read aloud.

Plans

- Delete Plan Sheet 3 of 3 - Fence Details and replace with the attached. Razor Wire replaced with 4 pt. barb wire.

Bid Proposal

- Delete pages 20 & 21 in their entirety and replace with the attached. Items have been revised to replace razor wire with barb wire. Bid Item 3 shall include all manual gates for **CHAINLINK & WOVEN WIRE** sections.



March 8, 2023

END

BID PROPOSAL
Lake Fork Fence Improvements
RFB #23-0701

Item	Quantity	Unit	Description	Unit Price	Total Price
<u>BASE BID ITEMS</u>					
1.	1	LS	Mobilization to Office site, insurance, performance, and payment bonds.		
			DOLLARS		
			CENTS	\$	\$ *
			Lump Sum		
2.	1	EA	Install new AUTOMATIC GATE 20' drive, 6' HDG chain link fence, posts, rails and hardware, top and bottom tension wire, including footings, all in accordance with plans and specifications for		
			DOLLARS		
			CENTS	\$	\$ *
			Each		
3.	3	EA	Install new MANUAL SWING GATE 20' drive, CHAIN LINK & WOVEN WIRE including, fence, posts, rails and hardware, bracing, including footings, all in accordance with plans and specifications for		
			DOLLARS		
			CENTS	\$	\$ *

4.	5,400	LN FT	<p>Install WOVEN WIRE fence with tee-posts and barbed wire fence including all hardware and connections, all in accordance with plans and specifications for</p>		
			DOLLARS		
			CENTS	\$	\$ *
			Per Linear Foot		
5.	54	EA	<p>Install anchored pipe posts, 2 7/8" single post .188" wall, anchored in concrete, all in accordance with plans and specifications for</p>		
			DOLLARS		
			CENTS	\$	\$ *
			Each		
6.	14	EA	<p>Install 3-post pipe brace includes complete installation of 3-post pipe brace, 2 7/8" .188" wall pipe, anchored in concrete, all in accordance with plans and specifications for</p>		
			DOLLARS		
			CENTS	\$	\$ *
			Each		
7.	1450	LF	<p>Furnish and Install Chain link Fence 6' HDG chain link fence, posts, barb wire, rails and hardware, top and bottom tension wire, including footings, all in accordance with plans and specifications for</p>		
			DOLLARS		
			CENTS	\$	\$ *
			Linear Foot		

*Do not extend unit prices or total out bid items. Show unit price in words and figures only. In case of discrepancy, the amount shown in words will govern.

